

CLARKE CREEK WIND FARM UPDATE

Capricorn Enterprise – Industry Lunch Friday October 25th 2019 Rockhampton

David Brown – Snr Project Manager, Clarke Creek Wind Farm







Goldwind Australia

Established in 2009

- 140 Employees
- 360MW wind + 10MW solar under operation
- 1,000MW wind + 20MW solar under construction
- >1,000MW under development
- Local staff, Sydney & Melbourne
- Project staff deployed locally in regional NSW, VIC and TAS.
- Strong relationship with key subcontractors
- In-house planning experts
- Advanced grid solutions



Goldwind Key Projects Operating

Mortons Lane Wind Farm Victoria

GW82 1.5MW 19.5MW Rated Capacity

Gullen Range Wind Farm New South Wales GW82 1.5MW + GW100 2.5MW 165.5MW Rated Capacity

Gullen Range Solar Farm New South Wales Gullen Range Wind Farm grid connection 10MW 22,000MWh/yr Capacity

White Rock Wind Farm New South Wales GW121 2.5MW 175MW Rated Capacity











Goldwind Key Projects Under Construction

White Rock Solar Farm New South Wales White Rock Wind Farm grid connection 20MW 44,000MWh/yr Capacity

Moorabool Wind Farm Victoria GW136 3.4MW 321MW Rated Capacity

Stockyard Hill Wind Farm Victoria GW140 3.6MW 530MW Rated Capacity

Cattle Hill Wind Farm Tasmania GW140 3.4MW 148MW Rated Capacity












Clarke Creek Wind Farm Overview



- Largest wind project in the Southern Hemisphere
- Project is approximately 170km north of Rockhampton;
- Wind and Solar Farm are separate projects;
- Up to 195 wind turbines located on the Broadsound Range (length ~ 55 km);



Clarke Creek Wind Farm Overview

The total project investment is around \$1.5 Billion;

Powering 600,000 Queensland homes, around 4% of Queensland Electricity.

Planning & Development achieved

Construction to commence early 2020 and be complete by 2023;

Estimated 300 - 350 jobs during the 30 - 36 months construction period and 20 full time jobs during operations.



Project Status

Project Milestones Completed

- Land access agreements
- State Government Development Approval
- Federal Government Environmental Approval (EPBC Act)
- Detailed Wind Modelling
- Database of over 700 companies and individuals potential suppliers and employees

Current Feasibility Work

- Geotechnical drilling and test pits
- Grid connection
- Refined road and electrical cabling design
- Preparation of lead contractor tender packages





Project Timeline (Indicative)

Future Project Milestones

- Now Final Tendering for Balance of Plant (Civil and Electrical) work.
- Late 2019 Likely off-site road works commence
- Early 2020 Target for Construction commencing

Next Steps

- ICN registration of interested contractors (Now)
- Complete Wind Turbine & BOP Tenders (early 2020)





Local Business Participation Program

- Identify capacity in the local community.
- Maximise opportunities for local suppliers to participate.

Stage One – Expressions of interest


 ICN Gateway https://clarkecreekwindfarm.icn.org.au

Stage Two – Industry Briefing Session

- More information on bidding process; opportunity to meet key project personnel.
- Database provided to main contractor and major subcontractors.

Stage Three – engagement of contractors


 The main contractor and/or major subcontractor may engage suppliers and subcontractors






Local Business Participation Program

- 17 work packages.
- Closing date extended from 8th March 2019.
- Over 700 expressions of interest from over 380 unique companies (Australia wide).





Indicative Contracting Structure





Construction Management

Balance of Plant



Civil - Earthworks

- Surveying, Clearing & Stripping
- Road construction
- Hardstand construction
- O & M Building



Foundations

- Excavation
- Steel reinforcement
- Concrete pour
- Backfill & Rehabilitation



Electrical

- UG Cable Installation
- Kiosk Installation
- Substation Construction



Construction Management

Logistics / Installation / Commissioning



Logistics

- Delivery
- Traffic Management
- Coordination



Installation

- Mechanical & Electrical works
- Pre-install erection
- Main Crane erection



Commissioning

- Inspections
- Testing
- Energisation/Generation



Construction – Some facts & figures



~120,000m³ of concrete to be poured



~120km of 33 kV underground cable to be laid



~170,000 tonnes of turbine components to be lifted



~ 250km of access tracks to be constructed



~1,100,000m² of hardstands to be constructed

Further information:

www.clarkecreekwindandsolar.com.au